CORRECTION TO 2016 CAMP PENDLETON REQUIREMENTS

16 SEPT 2016 –

1) ROOFING and EAVES Page 211
   The sheet (field) membrane shall have a nominal thickness of 60 mils (not 80 mils)